



HAMILTON  
HOUSTON  
LOWNIE



## TRINITY UNITED METHODIST CHURCH MASTER PLAN & RENOVATIONS

Grand Island, New York

HHL prepared a facilities master plan report for the church which outlined various repair issues, as well as space and systems utilization. Recommendations included roof replacement, mechanical and fire alarm repairs, and a serious structural condition at the sanctuary laminated beams, due to roof leaks.

The first project included the repairs to the structural member, and the elimination of the cause for the deterioration. The existing unique chevron-shaped stained glass windows had no deterrent at the window curb to prevent ice & water from penetrating. HHL redesigned the window openings to create a curb, and reinstalled the stained glass on the

interior side of new clear insulated glass aluminum windows.

Future phases include complete roof replacement and systems upgrades.

*Project Size:* 15,000 sf

*Project Cost:* \$300,000

*Complete:* 2005

*Client:* Trinity United Methodist Church

*Reference:* Pastor Paul Robinson

*Telephone:* (716) 773-3322